```
 Updated to latest. Got 47 features, 420 bugfixes, and 169 other
changes.
  code.claude.com/docs/en/changelog for details

  Introducing Sonnet 5.5
  Sonnet 5.5 is here, and it's faster and excels at well-scoped tasks.
Opus 5.5 is still your default. Switch with /model.
  1 more notice hidden

❯ Finance: A wealth management firm wants a solution that helps
advisors quickly get up to
  speed on a stock-fetching current quote data and summarizing key
information from recent
  SEC filings.
  You have flexibility in how you build your solution. Choose the
approach that best demonstrates
  your capabilities.
  Examples of approaches:
  • No-Code / Low-Code: n8n
  • AI-Native Tools: Custom GPTs, Gemini, Claude Projects, NotebookLM,
Perplexity
  • Code + Frameworks: VS Code, Python, LangChain, FastAPI, Streamlit
  • Hybrid: Any combination of the above
  based on this use case. I'm going to build a project. Now act as a
senior AI engineer. check for what kind of requirements with the
minimal resources, cost effifent way to build. And also mention any
kind of improvements and architectural choices.

● Login expired · Please run /login

✻ Worked for 0s · done 12:13 PM

❯ run /login

● Login expired · Please run /login

✻ Crunched for 0s · done 12:14 PM

❯ /login
  ⎿  Login successful


I'll check current Claude model pricing first so the cost advice isn't
from memory.

● Skill(claude-api)
Successfully loaded skill · 1 tool allowed
13 skills available

Stock briefing tool: requirements, cost and architecture
```

What I'd build

A deterministic pipeline, not an agent and not RAG. The inputs are small, bounded and well structured: one quote and a handful of filings for a known ticker. A fixed fetch → extract → summarize flow is cheaper, easier to test and more predictable than letting a model decide which tools to call. It also means the model call has no tools, so a malicious string inside a filing can't trigger anything.



Requirements

Functional
- Input a ticker and get a current quote: price, change, volume, market cap, 52-week range, and an "as of" timestamp.
- Get a summary of the latest 10-K, the latest 10-Q and the 8-Ks from the last ~90 days. Cover business, financial drivers, risks and material events.
- Every claim links back to its source filing.

Non-functional
- A brief in under about 20 seconds cold, and instantly on a cache hit.
- Numbers must be correct. Financial figures come from XBRL, never from the LLM.
- Compliance: label the output as not investment advice, keep an audit log of what was shown, and have compliance review it before it goes near client communications.

Cost-efficient stack (about $0 infrastructure)

Layer	Choice	Why

Filings	SEC EDGAR APIs (free, no key)	Needs a User-Agent header with your contact email, and a limit of ~10 requests/sec.
Parsing	edgartools	Gives you 10-K/10-Q item sections without hand-rolled HTML parsing.
Quotes	Finnhub free tier for a demo, or yfinance for a quick prototype	yfinance is unofficial and can break or hit ToS issues. Production needs a licensed feed. Check current free-tier limits before committing.
LLM	Sonnet 5.5 (claude-sonnet-5-5, $2 / $10 per MTok), Haiku 4.5 for 8-K triage	See below.
Cache	SQLite or diskcache	Filings never change, so cache by accession number.
UI / host	Streamlit on Community Cloud or locally	No servers to run. Add FastAPI only if other systems need to call it.

Token cost, my estimate. Don't send whole filings. Send only Item 1A, Item 7 and the 8-K bodies, which is roughly 60–80K input tokens per ticker. Sonnet 5.5 costs about $0.15–0.20 per cold briefing. Haiku 4.5 costs about half that, and Opus 5.5 ($4 / $20) about twice. Sonnet is the sweet spot for summarization, and Opus for a "deep dive" mode is only a 2x premium.

Cost levers, in order of impact:
1. Section extraction. This is the biggest saving, since a full 10-K is 100K+ tokens.

2. Per-filing summary cache. Summarize each filing once, ever, and share it across all advisors. The advisor-facing brief then merges a few small cached summaries, so a repeat lookup costs about $0.
3. Low effort. Set output_config.effort to low or medium for summarization. Sonnet 5.5 defaults to high, which burns thinking tokens you don't need here.
4. Prompt caching (cache reads are $0.20/MTok) for follow-up Q&A on the same filing.
5. Batch API (50% off) to pre-warm a watchlist overnight.

Architectural choices I'd defend

- Numbers from XBRL, narrative from the LLM. This removes the most damaging failure in finance, which is a hallucinated figure.
- Structured output. Return JSON with fields like business_overview, key_changes, risks[], material_events[] and outlook, so the UI is consistent across tickers.
- Grounding without the Citations API. Citations can't be combined with structured outputs (it returns a 400). Instead, have each JSON item carry a short verbatim evidence_quote and a section reference. Then check each quote is a substring of the source text in code. Anything that fails is dropped or flagged. It costs nothing and catches fabrication.
- Long context over a vector DB. Filtered filings fit comfortably in the context window, so skip embeddings and a vector store. Revisit RAG only if you add multi-year or cross-company search.
- Adapter interfaces for quotes and filings. Swapping Finnhub for Polygon or Bloomberg later becomes a one-file change.
- n8n works but isn't ideal here. Section extraction, caching and quote verification are awkward in no-code. Python is cleaner and easier to test.

Edge cases that will bite you

- Share classes (GOOG/GOOGL) map to one CIK.
- Foreign issuers file 20-F and 6-K instead of 10-K and 10-Q.
- Recent IPOs may have only an S-1.
- ETFs have no 10-K.
- 10-K/A amendments exist.
- Fiscal years differ between companies.
- Inline-XBRL HTML flattens tables.
- A quote shown after hours should say it is stale.

Improvements, roughly in priority order

1. Eval harness. Build a golden set of 15–20 tickers. Check numbers against XBRL, track the quote-verification pass rate, and add a small human rubric. This is what separates a demo from something an advisor can trust.
2. YoY risk-factor diff (this 10-K vs. the prior one). Advisors value

this highly, and it is cheap to build.
3. Earnings 8-K (Item 2.02) summary with guidance changes.
4. Form 4 insider activity and 13F ownership.
5. Peer comparison using XBRL frames.
6. Conversational Q&A over the loaded filing. This is the one place a tool-calling loop is justified.
7. Observability (log usage, cache hit rate, cost per brief), PDF one-pager export, watchlist alerts when a new 8-K lands, and portfolio-aware context. Do the last one only after a data-governance review, so client data never goes into prompts unreviewed.

Next step

I'd scaffold this in Python with Streamlit. Tell me if you want that, and which quote provider you prefer, Finnhub (needs a free API key) or yfinance (no key, but fragile). I can also turn this write-up into a shareable page if you want to send it around.

✻ Cooked for 1m 23s · done 12:15 PM

❯ the approch that I'm thinking is for parsing the documents lets work with both python parsing and ocr and Azure AI Document Intelligence in order to handle complex image or table kind of data. for the embedding model I'll go with context aware chunking with open ai embedding 3 and vector database go with milvus and for the frontier model use gemini. for the caching use redies also build a frontend single page application for the customer side. Also intergate langsmith based model monitoring. And project should be based on langchain/langraph framework.
12 skills available

Review of your stack

The stack is workable, but it's about 3x the moving parts of what I first proposed. Build it in phases so you always have something demoable. A few pieces earn their place only in specific cases, so route to them instead of running them everywhere.

Component verdicts

Component	Verdict	Note
Python parsing	Keep, as the primary path	EDGAR filings are born-digital HTML with real <table> tags. Parsing the HTML is more accurate than OCR.

Azure Document Intelligence	Keep, as a fallback only	Use it for PDF exhibits, image-based slides, scanned or advisor-uploaded PDFs.
OCR (separate)	Drop as a separate path	Azure DI already includes OCR (its Read/Layout models), so a second engine adds nothing.
OpenAI embeddings-3	Keep, use -small	Embedding a 10-K costs well under a cent. Measure -large on your eval set before paying for it.
Milvus	Keep, but start on Milvus Lite	The corpus is small (tens of thousands of chunks). Lite and standalone share the pymilvus API, so you can move up to standalone or Zilliz Cloud later.
Gemini	Keep	A Flash-tier model for per-filing summaries and a Pro-tier model for deep dives. Check current pricing. LangChain makes the model a config value, so you can benchmark alternatives later.
Redis	Keep, as a hot cache and checkpointer	It is not durable storage for summaries.
SPA	Keep	A React + Vite + TypeScript app talking to FastAPI over SSE streaming.

LangSmith	Keep	It also gives you the eval harness (datasets and evaluators) I recommended earlier.
LangChain/LangGraph	Keep, but only where the graph earns it	See below.

Parsing


Azure DI's Layout model costs roughly $10 per 1,000 pages (verify current pricing). A 150-page 10-K would cost about $1.50 to parse, around 8x the LLM cost of summarizing it. So don't run it on everything. Add a router node that sends a document to Azure DI only when the HTML parser finds no text layer, finds image-only content, or fails to extract tables cleanly. Azure DI's free tier should cover a demo.


Chunking, retrieval and Milvus

- Chunk along the filing structure. Split by Item, then subsection, then paragraph, at roughly 500–800 tokens.
- Keep each table whole, with its caption and footnotes. Store the table as markdown in the payload. Embed a one-line description of it, because raw tables embed poorly.
- Prefix every chunk with a deterministic header, such as AAPL | 10-K FY2025 | Item 7 MD&A | Liquidity. This gets most of the benefit of contextual retrieval for free. Only add LLM-generated chunk context if your eval shows a gain.
- Store metadata (ticker, CIK, form type, accession number, period, item) and pre-filter on it. A question about AAPL's 10-K should never retrieve from a different company's filing.
- Use hybrid search. Dense-only retrieval misses exact terms, and Milvus supports sparse/BM25 alongside dense vectors. Consider adding a reranker.
- Route numeric questions to XBRL, not to RAG. Retrieval is unreliable for exact figures.
- Skip RAG for the briefing itself. The filtered filing text fits in Gemini's long context. Use RAG only for follow-up Q&A.

LangGraph design

Use two graphs, because ingestion is slow and querying must be fast:





LangGraph earns its place on parallel fan-out (Send), parser routing, the verify-and-retry loop, checkpointing, and the chat agent. Everything else is plain functions. A cold ticker may take 30–90 seconds, so stream progress to the SPA and pre-ingest a watchlist.

Redis, LangSmith and the frontend

- Redis holds the quote cache (60s TTL), a shared EDGAR rate limiter (10 requests/sec across workers), and the LangGraph checkpointer. Don't semantic-cache anything with prices or figures. Near-duplicate queries would serve stale or wrong numbers. Keep durable summaries in the vector store or a database.
- LangSmith: tracing is a few env vars. Tag each run with ticker, form type, model and cache-hit. Capture advisor thumbs-up/down as feedback. The free tier is limited (about 5K traces/month last I knew). Traces send prompts and filing text to a SaaS, which is fine for public data. Never log client-identifying data.
- SPA: build a ticker search, a quote card, tabbed filing summaries, a citation drawer that opens the filing at the quoted passage, and a chat panel. Keep every API key in the backend, and put real auth (OIDC) in front of it even for a demo.

Phased plan

1. Core. EDGAR HTML parsing, XBRL, quote, Gemini structured summary with quote verification, Redis cache, LangSmith tracing, and a minimal SPA. No Milvus and no Azure DI yet.
2. Q&A. Chunking, embeddings, Milvus Lite, hybrid retrieval, and chat with citations.
3. Hardening. Azure DI fallback, a LangSmith eval set (15–20 tickers), and a move to Milvus standalone or Zilliz.

Risks

- Operations. You will have six services (Azure, OpenAI, Gemini, Milvus, Redis, LangSmith), a frontend and an API. That means more keys, more failure points, and three LLM-vendor data agreements to review. Keep the adapters thin.
- "Customer side" compliance. If end clients see this rather than advisors, the compliance bar rises. Retail-facing content needs disclaimers, no personalized buy/sell language, and compliance review. Add an output guard that refuses "should I buy X?" questions.
- Version drift. LangChain and LangGraph move quickly, so pin your versions.

Do you want me to scaffold Phase 1? If so, tell me whether "customer" means the advisor or the end client, since that changes the guardrails I'd build in from the start.

✻ Cogitated for 1m 4s · done 12:36 PM

❯ Ask me some follow-up questions in the architecture.

● User answered Claude's questions:
· Who will actually use the frontend? This decides auth, compliance guardrails, and how much hallucination risk is acceptable. → Advisors only (Recommended)
· What is this project for? This sets how much of the 3-phase plan to build and how much infrastructure to invest in. → Interview or take-home demo
· How fresh do the stock quotes need to be? → Delayed (~15 min) is fine
· Which of these features are in scope? Select all that apply. → Evidence based summerization as the response. it should hold the citation for that exact do.

I've confirmed the scope: an evidence-based summarizer where every claim must cite its exact source, so I'm centering the architecture on deterministic passage IDs, quote verification against stored text, and auto-generated source URLs rather than model-invented links. Since Milvus isn't needed for this scope, I'll adjust the third phase of the plan accordingly. · summary

● User answered Claude's questions:
· With scope narrowed to evidence-based summaries, how should Milvus and embeddings be used? → vector DB + Fact based evidence. if its excel dataset should mention row number if its doc cite that doc.
· How precise should each citation be in the UI? → Section-level
· When a claim's citation fails verification (the quote isn't found in the cited passage), what should happen? → Retry once, then drop
· How will the demo be delivered and reviewed? This decides Milvus and Redis deployment. → For the demo lets work locally.

Updated plan based on your answers.

- Retrieval: Milvus with facet-based evidence retrieval.
- Citations: section-level in the UI. I'll still keep the verbatim quote in the payload for verification, which costs nothing.
- Failed claims: retry once, then drop. I'll re-prompt only the failed claims, with their passages, not the whole brief.
- Delivery: local, with docker compose.
- New requirement: Excel sources cite the row number, and documents cite the document.

That last requirement adds a second kind of source. Excel rows chunk differently from prose, and they verify differently:

```
INGEST (per ticker, skip accessions already cached in Redis)
 resolve_ticker ─┬─ fetch_quote
                 └─ fetch_filing_index ─(Send per filing)─▶ fetch
                      ─▶ route_parser ─┬─ html_parser  ─▶ passages
(doc)
                                       ├─ excel_parser ─▶ row records
(sheet, row)
                                       └─ azure_di     ─▶ passages
(PDF fallback)
                      ─▶ chunk ─▶ embed ─▶ upsert_milvus

BRIEF (online)
 retrieve_per_facet (filter: ticker, accession, source_type)
   ─▶ summarize (Gemini, structured claims + source IDs)
   ─▶ verify ─(failures & retry<1)─▶ re-prompt failed claims ─▶ verify
   ─▶ drop remaining, show count ─▶ render
```

- One citation type, two variants.
  - A document citation is {accession, form, date, item, link}.
  - A sheet citation is {file, sheet, row}.
  - The UI renders them as chips such as 10-K · Item 7 · filed 2025-10-31 ↗ or Financial_Report.xlsx · Balance Sheet · row 12.
- Excel rows chunk one row per record. Repeat the sheet name and column headers in each row so it stands alone when embedded.
- Excel verification is stricter than documents. For documents, check that the quote is a substring of the cited passage. For sheets, check that the cited value equals the cell at that sheet, row and column.
- Row numbers need care. Cite the row number as Excel displays it (openpyxl's cell.row), not the pandas index. Otherwise citations will be off by the header offset.

I need three things before I can finalize the design:

● User answered Claude's questions:
· What are the Excel datasets? This decides where they come from and

how rows are cited. → combination of excel and pdf.
· Which Milvus setup for the local demo? → I'll push it later into github
· Which accounts and API keys do you already have? This tells me what can be built and tested end to end. → Gemini API key

Before the final design, I'll save these decisions to project memory so they carry into later sessions.

  Recalled 1 memory, wrote 2 memories

Here's how I read your last answers, and what they change.

- Excel and PDF: both are inputs. You didn't name the source, so I'm assuming EDGAR's Financial_Report.xlsx per filing, plus PDF exhibits or uploaded files. Tell me if that's wrong.
- Milvus: your answer was about pushing to GitHub, so I'm reading it as "make the repo clone-and-run friendly." That means Milvus Lite by default, with MILVUS_URI available to point at standalone later.
- Accounts: you only have a Gemini key.

Four adjustments

1. Embeddings. Without an OpenAI key, I'd default to Gemini's embedding model behind an Embeddings interface. Check its current name and limits. OpenAI text-embedding-3-small becomes a config switch, and the demo needs one API key instead of two. Record the embedding model and dimension per Milvus collection, because switching models means re-embedding.
2. PDFs. I can't test Azure Document Intelligence without an Azure subscription. The default PDF parser would be local: PyMuPDF for text, pdfplumber for tables, and Tesseract OCR for scans. I'd write the Azure adapter behind AZURE_DI_* env vars and mark it untested until you have credentials. A free Azure account would let us test it. PDF citations would be file + page + heading. Gemini vision is a last resort for image-only tables, because the quote check needs a deterministic text layer.
3. Quotes. To avoid another signup, the default adapter would be yfinance (no key), labeled "delayed, unofficial." Finnhub is a config switch. I'd pick the demo default for convenience, and it's the fragile option.
4. GitHub-ready.
   - docker compose runs Redis only. Milvus standalone sits behind an optional profile.
   - Ship a .env.example.
   - Gitignore .env, milvus.db and data/.
   - Read the SEC User-Agent contact from env, so your email isn't committed.
   - LangSmith, Azure and OpenAI all degrade gracefully when their keys are absent. LangSmith's free signup takes about two minutes.

Revised phases

1. Core, end to end.
   - EDGAR HTML and Financial_Report.xlsx parsing, with passage IDs and sheet-row records.
   - Milvus Lite with Gemini embeddings and facet retrieval.
   - Gemini structured claims, then verify, retry once, and drop.
   - Quote adapter, Redis cache, FastAPI with SSE, and the React SPA.
2. PDF path. Local parser first, then the Azure adapter behind its flag. Evals and polish. A LangSmith eval setDME with a diagram, and the GitHub push.

Update available! Run: brew upgrade claude-code

⚠ 7 MCP servers need authentication · run /mcp

  Opus 5.5 is now your default model and it draws down usage faster than Sonnet 5. Switch anytime with /model.
  1 more notice hidden

❯ financial-statement-data-sets.pdf
  2026q2.zip
  2026q1.zip
  2026q3.zip

  datasets.

I'll start with the project memory and the files in the directory.

  Listed 1 directory, recalled 1 memory

The files aren't at the top level. I'll check the stock-briefing folder and search for them.

  Listed 1 directory

The files are in ~/Downloads. I'll list what's in each zip and compare the two 2026q3 copies, then read the PDF.

  Read 1 file, ran 1 shell command

pdftoppm isn't installed, so I'll look for another way to read the PDF. For the zips, I'll sample the first rows of each file with unzip -p instead of extracting about 2.4 GB.

  Ran 2 shell commands

These are the SEC Financial Statement Data Sets (sub, num, pre, tag). Next I'll pull the text out of the PDF and get per-quarter stats from sub.txt.

  Ran 2 shell commands

Quartz isn't available to the system Python. I'll try PDFKit through JXA instead.

  Read 1 file, ran 1 shell command

I've read the PDF and sampled the three zips, but I haven't extracted or changed anything. The files are in ~/Downloads, not the project folder.

What they are: the SEC Financial Statement Data Sets for 2026 Q1–Q3. Each zip holds four tab-delimited tables plus a readme.htm:

Table	Contents
sub.txt	One row per filing: CIK, company name, SIC, form, period, filed date, accession (adsh)
num.txt	The numeric values from the primary financial statements, keyed by accession, tag, period and quarters covered
pre.txt	How each line item was presented and ordered on the statements
tag.txt	XBRL tag definitions and labels

Per quarter:

	Filings	Companies (CIKs)	Filed	Main forms	Unzipped
2026q1	6,169	5,750	Jan 2 – Mar 31	4,262 10-K, 972 10-Q	672 MB
2026q2	7,714	6,179	Apr 1 – Jun 30	5,321 10-Q, 731 11-K, 570 10-K	718 MB
2026q3	6,516	6,008	Jul 1 – Sep 30	5,263 10-Q, 370 6-K, 344 10-K	986 MB

No accession numbers repeat across quarters, so the three can be combined directly.

Things that matter for the stock briefing:
- No tickers. sub.txt has only CIK and name. You'd need a ticker-to-CIK lookup, such as SEC's company_tickers.json. The instance filename often starts with the ticker (for example amd-20260627_htm.xml), but that isn't reliable.
- Numbers only. The data covers the primary statements: balance sheet, income, cash flow, equity and comprehensive income. It has no risk factors, MD&A or guidance text, so the facet-based evidence retrieval from Milvus would still need the EDGAR HTML filings. The PDF says each filing's folder is sec.gov/Archives/edgar/data/{cik}/{adsh without dashes}/, so sub.txt can supply the links.
- As filed, not cleaned. The PDF warns of redundancies and inconsistencies, and prevrpt=1 marks filings that were later amended. Amendments would need handling.
- Coverage ends Sep 30, 2026. Filings from October aren't in these files.
- Size. num.txt is 560–875 MB per quarter, so you'd filter by CIK or load it into SQLite or DuckDB rather than read it whole.
- Duplicate. ~/Downloads/2026q3 (1).zip is byte-identical to 2026q3.zip (same SHA-1). I left it alone.

Your project notes say the Excel source was still unconfirmed. These files are tab-delimited text, not Excel. Do you want them to be the source of the figures, with the claim check changed from Excel cell and row to num.txt row (accession, tag, period)?

If so, I can extract them into stock-briefing/data/raw/ and write an ingest that maps ticker to CIK and loads the latest filings into SQLite. Or tell me what you had in mind.

✻ Worked for 1m 9s · done 12:58 PM

※ recap: The goal is the evidence-cited stock briefing app, and I just inspected your SEC Financial Statement Data Sets (2026 Q1–Q3) without changing anything. Next, I need you to confirm whether they replace Excel as the figures source, then I'll extract and ingest them. (disable recaps in /config)

❯ retry.

The only step that failed last turn was the native PDF read, which needed pdftoppm. I'll retry that.

  Read 1 file, listed 1 directory

The native PDF read fails the same way: pdftoppm (part of poppler) isn't installed on this Mac, so a retry can't work until it is. It doesn't block anything, because I already extracted all 10 pages of text through macOS PDFKit last turn. The summary I gave you covers the whole PDF.

If you want the native reader to work, run this yourself with the ! prefix: ! brew install poppler

I wasn't sure what you meant by "retry", so I stopped here. Did you mean one of these?
- Re-run the whole summary. Say so and I will, after the poppler install if you want it.
- Go ahead with the ingest. I'd extract the three zips into stock-briefing/data/raw/<quarter>/ (the folder is empty now) and build the ticker-to-CIK lookup and SQLite load.
- Something else that failed on your side. The IDE connection to Claude Code also failed at the start of this session, which I can't retry from here.

✻ Brewed for 12s · done 1:06 PM

※ recap: Goal: build the evidence-cited stock briefing app, and I'm now looking at the SEC 2026 Q1–Q3 financial statement datasets you downloaded, which I've inspected and summarized but not extracted. Next, I need you to confirm I should extract them into the project and build the ticker-to-CIK ingest. (disable recaps in /config)

❯ it is intalled.

  Read 1 file

The native read works now. I'll read the remaining pages too, so I've seen the whole PDF as rendered.

  Read 1 file

The PDF now reads natively, and all 10 pages match the text I extracted last turn. Nothing in my earlier summary changes.

Two details from the rendered pages that matter for the ingest:
- Scale: num.value is unscaled and limited to four decimal places. qtrs=0 marks a point-in-time value (balance sheet), and qtrs=4 is a full year.
- Consolidated figures: in num, a blank segments and blank coreg means the consolidated entity. A query for a company's headline figures should filter on both being empty. Otherwise segment and co-registrant rows get mixed in.

Do you want me to go ahead with the ingest? That means extracting the three zips into stock-briefing/data/raw/<quarter>/, mapping ticker to CIK, and loading the latest filings into SQLite. Or point me at something else.

✻ Sautéed for 10s · done 1:15 PM

❯ yes

First I'll look at what already exists in the project so the ingest matches it.

  Ran 1 shell command

The project already has a lot of code. I'll read the parts the ingest has to fit into: config, models, the EDGAR source and the statements parser.

  Read 1 file, ran 1 shell command

The project already fetches ticker-to-CIK from EDGAR and cites statement rows. I'll check the remaining pieces (cache, verify, script and test style), disk space, and the row shape of the raw files.

  Ran 2 shell commands

Disk space is fine (315 GB free). I'll extract each zip into its own new directory under data/raw/.

  Ran 1 shell command

Line counts check out (6,169 filings plus header). Before designing

the schema, I'll verify field counts per row and check how many num rows are consolidated-only. · summary

  Ran 1 shell command

Two num rows in q1 have 11 fields instead of 10, which suggests a stray tab. I'll look at them before deciding how to handle it.

  Ran 1 shell command

I found malformed rows with stray tabs in segments that I can rebuild from fixed trailing fields, confirmed only ~41% of num rows are consolidated (so I'll keep segment rows too), and noted there's no .env/cached ticker file yet, so I won't guess tickers from filenames. Next I'll check whether the venv has everything the tests need. · summary

  Ran 1 shell command

The baseline is 47 tests passing. I'll write the store module first.

● Write(briefing/sources/fsds.py)
Wrote 304 lines to briefing/sources/fsds.py
"""SEC Financial Statement Data Sets (FSDS): bulk XBRL figures loaded into a local SQLite file.

The SEC publishes one zip per calendar quarter (sub/num/pre/tag tab-delimited text) holding the
numbers from the primary financial statements of every XBRL filing, "as filed". This module
loads the 10-K/10-Q family into SQLite and answers the two questions the briefing needs:
which filings are the latest for a company, and what the consolidated statement lines say.

Things worth knowing before trusting a number from here:
  * The SEC file has no ticker column. Ticker -> CIK comes from SEC's company_tickers.json
    (see `load_tickers`), never from guessing at XBRL instance file names.
… +313 lines

Next is the CLI script, written in the same style as scripts/smoke_real.py.

● Write(scripts/ingest_fsds.py)
Wrote 75 lines to scripts/ingest_fsds.py
"""Load SEC Financial Statement Data Sets (extracted quarters) into data/fsds.sqlite.

```
Get the quarters from https://www.sec.gov/dera/data/financial-
statement-data-sets and unzip each

    python scripts/ingest_fsds.py                      # every data/
raw/<YYYYqN> folder
    python scripts/ingest_fsds.py --quarters 2026q3    # just one (re-
running a quarter replaces
 it)

Ticker -> CIK needs SEC's company_tickers.json. If --tickers is not
given, the copy the app cach
es
… +76 lines

● Update(briefing/config.py)
Added 8 lines
    def uploads_dir(self) -> Path:
        return self.data_dir / "uploads"

    @property
    def fsds_raw_dir(self) -> Path:
        return self.data_dir / "raw"

    @property
    def fsds_db(self) -> Path:
        return self.data_dir / "fsds.sqlite"


@lru_cache
def get_settings() -> Settings:
    return Settings()

● Write(.gitignore)
Wrote 12 lines to .gitignore
.venv/
.env
__pycache__/
.pytest_cache/

# Large or generated data: the raw SEC quarters alone are ~2.4 GB
data/raw/
data/cache/
data/uploads/
data/*.sqlite
… +2 lines

Now the tests. They build a tiny synthetic quarter that includes the
real edge cases I found: a stray tab, a stray double quote, a 20-F
that should be filtered out, and an amendment.
```

● Write(tests/test_fsds.py)
Wrote 168 lines to tests/test_fsds.py
import json

import pytest
from briefing.sources.fsds import FsdsError, FsdsStore, connect,
ingest_quarter, load_tickers

SUB_HEAD = "adsh cik name sic countryba stprba cityba zipba bas1 bas2
baph countryma stprma city
ma zipma mas1 mas2 countryinc stprinc ein former changed afs wksi fye
form period fy fp filed ac
NUM_HEAD = "adsh tag version ddate qtrs uom segments coreg value
footnote".split()
PRE_HEAD = "adsh report line stmt inpth rfile tag version plabel
negating".split()
TAG_HEAD = "tag version custom abstract datatype iord crdr tlabel
doc".split()
… +178 lines

  Ran 1 shell command

All 7 pass. Now the real run on all three quarters, in the background
since it will take a few minutes.

  Ran 1 shell command

While that runs, I'll add a short README section so the next person
can reproduce this.

  Ran 1 shell command

● Write(README.md)
Added 24 lines
Stock Briefing

SEC Financial Statement Data Sets (bulk XBRL figures)

Quarterly zips from <https://www.sec.gov/dera/data/financial-
statement-data-sets> hold the numb
ers from the primary
financial statements of every XBRL filing. Unzip each quarter into its
own folder and load them
 into SQLite:

```bash
mkdir -p data/raw/2026q1 && unzip 2026q1.zip -d data/raw/2026q1   #
repeat per quarter
python scripts/ingest_fsds.py                                      #
writes data/fsds.sqlite
```

```

- Only 10-K, 10-Q and their amendments are loaded (`--forms` to change). Re-running a quarter r
eplaces it.
- The SEC files have no tickers. Pass SEC's `company_tickers.json` with `--tickers`, or let the
 app cache it at
  `data/cache/edgar/company_tickers.json`.
- `data/raw/` is about 2.4 GB for three quarters and is git-ignored. So is the SQLite file.
- Figures are "as filed". `latest_filings` returns each company's newest 10-K and newest 10-Q;
an amendment wins if newer.

```python
from briefing.sources.fsds import FsdsStore
store = FsdsStore("data/fsds.sqlite")
cik = store.cik_for_ticker("AAPL")
latest = store.latest_filings(cik)                # newest 10-K and 10-Q
income = store.statement(latest[0]["adsh"], "IS")  # consolidated lines, R-file number + line +
 values per period
```

  Ran 1 shell command

Foreground sleeps are blocked. The background job will notify me when it finishes, so I'll just check the interim output.

  Read 1 file

I mistyped the path. Correcting it:

  Read 1 file

The output's empty just because stdout gets buffered when piped, so nothing shows until the first quarter completes. I'll run the full test suite now to confirm the config change didn't break anything.
· summary

  Ran 1 shell command

All 54 tests pass (the original 47 plus 7 new). To wait on the ingest properly, I'll load the Monitor tool.

The Monitor docs say one-shot waits belong in a background until loop, so I'll do that. It exits when the ingest prints its final line or fails.
```

  Ran 1 shell command

The ingest is still running (all three quarters, about 11 million num rows). I'll pick up from the completion notification and then check the loaded data against the raw files.

✻ Cogitated for 5m 15s · done 1:20 PM

● Background command "Ingest all three raw quarters into SQLite" completed (exit code 0)

  Listed 1 directory

● Background command "Wait for the ingest to finish and show its output" completed (exit code 0)

The run completed in ~47 seconds, with repaired counts (2, 12, 22) matching the stray-tab rows found earlier and no rejections. I'll now independently verify the load by recounting rows with awk and cross-checking one filing's figures against the raw file. · summary

  Ran 2 shell commands

Every check passes. I'll record this in the project memory so it isn't re-derived next session.

  Wrote 1 memory

The three quarters are loaded into stock-briefing/data/fsds.sqlite (3 GB). I haven't connected them to the briefing graph yet, and ticker lookups return nothing for now.

What I checked:
- Counts: I recounted rows from the raw files with awk and they match the database exactly. That's 17,011 filings and 9.5 million facts across the three quarters.
- Spot check: AMD's latest 10-Q (0000002488-26-000123) matches the raw file, including the segment rows (for example, Q2 2026 net revenue of $11,536,000,000 and six-month revenue of $21,789,000,000).
- Bad rows: 36 num rows had a stray tab (2, 12 and 22 across q1–q3). I rebuilt them rather than shifting their columns, and none were rejected.
- Tests: all 54 pass (47 existing plus 7 new in tests/test_fsds.py).

What was added:
- Raw files: extracted to data/raw/2026q1, 2026q2 and 2026q3.
- Loader: briefing/sources/fsds.py loads only 10-K, 10-Q and their amendments. Re-running a quarter replaces it. scripts/ingest_fsds.py runs it, and the whole load took about 47 seconds.

- Lookups: FsdsStore.latest_filings(cik) returns the newest 10-K and newest 10-Q, and an amendment wins if it's newer. FsdsStore.statement(adsh, "IS") returns the consolidated lines (a statement query takes about 1 ms). Each line carries its EDGAR R-file number (AMD's income statement is R2), its line number and its values by period.
- Housekeeping: .gitignore excludes the 2.4 GB of raw data and the SQLite file, and a short README section covers the steps.

Open items:
1. Ticker lookups return nothing yet. company_tickers.json isn't cached, and SEC requires a User-Agent with a contact. I didn't use your email for that. Run this yourself (with ! if you like), then re-run scripts/ingest_fsds.py:
   curl -A 'Your Name you@example.com' https://www.sec.gov/files/company_tickers.json -o data/cache/edgar/company_tickers.json
2. Citations for FSDS figures need a decision. The verification step checks quoted numbers against a cited row and shows "row N". FSDS gives an R-file and line, not an Excel row, so a citation would read like "R2 · line 1". Do you want FSDS to replace the Excel source or sit beside it? Once you choose, I can wire it into the graph.
3. Size. The database is bigger than the raw text because segment strings repeat on every row. If that bothers you, I can trim it.

I also updated the project memory with the dataset location and the open decisions.

✻ Brewed for 1m 27s · done 1:22 PM

※ recap: We're building an evidence-cited stock briefing app, and I just loaded the SEC quarterly datasets (2026 Q1 to Q3) into a local SQLite database, verified against the raw files. Next, fetch the SEC ticker file so company lookups work, then decide how those figures get cited. (disable recaps in /config)

❯ create a .env file for my api

I'll check which environment variables the code reads, so the file covers them.

  Listed 1 directory

The first search failed on zsh globbing, so I'll check the frontend separately.

  Ran 1 shell command

The frontend reads no environment variables. Everything goes through briefing/config.py, which loads .env from the project root. I'll write the real .env and a committable .env.example.

● Write(.env)
Wrote 32 lines to .env
Local settings. This file is git-ignored; keep real keys here and
never commit them.
Only the two required values below need filling in; everything else
has a working default.

--- Required

SEC EDGAR requires a descriptive User-Agent that includes a contact
email.
SEC_USER_AGENT=Your Name your-email@example.com

Gemini API key (https://aistudio.google.com/apikey). GEMINI_API_KEY
is accepted as an alias.
GOOGLE_API_KEY=
… +22 lines

● Write(.env.example)
Wrote 31 lines to .env.example
Copy to .env and fill in the two required values. .env is git-
ignored.

--- Required

SEC EDGAR requires a descriptive User-Agent that includes a contact
email.
SEC_USER_AGENT=Your Name your-email@example.com

Gemini API key (https://aistudio.google.com/apikey). GEMINI_API_KEY
is accepted as an alias.
GOOGLE_API_KEY=

--- Models

… +21 lines

I'll confirm the app parses it, without printing the key, and re-run
the tests since .env now gets loaded.

  Ran 1 shell command

I created stock-briefing/.env. The app loads it, but two values are
still placeholders for you to fill in:

1. GOOGLE_API_KEY= is empty. Paste your Gemini key here
(GEMINI_API_KEY also works as the name). I don't have your key and
didn't guess one.
2. SEC_USER_AGENT=Your Name your-email@example.com needs your real

name and contact email. SEC requires this on every request, and the placeholder will probably get blocked. I left your email out because it would be sent to SEC. This value is also what the company_tickers.json download needs.

What's in the file:
- The Gemini model and embedding settings (gemini-flash-latest, gemini-embedding-001, 768 dimensions).
- The default Milvus Lite file and the local Redis URL. If Redis isn't running, the app uses an in-process cache.
- The quote provider order, with FINNHUB_API_KEY empty so Finnhub is skipped.
- LangSmith tracing off.

What I checked:
- Loading: I ran the config loader against the file and the values load as expected.
- Tests: all 54 tests still pass.

I also added .env.example with the same layout, so a clone of the repo shows what to fill in. .env is already in .gitignore, so your keys stay out of GitHub. This folder isn't a git repo yet, so I couldn't test the ignore rule.

✻ Cooked for 44s · done 1:29 PM

❯ how to set Milvus URI

I'll check how the store uses the URI and what your .env currently says, so I answer from the code.

  Listed 1 directory

Set it in stock-briefing/.env, line 20 (MILVUS_URI=). There are two options, and you don't need to change anything to run the demo.

Option 1: Milvus Lite (what you have now). Leave it empty. The app then uses a local file at data/milvus.db, which is created on the first run. Milvus Lite is already installed in your venv, and this matches your "local, no extra services" setup.

MILVUS_URI=

Option 2: a standalone Milvus server. Point it at the server's address. 19530 is Milvus's default port.

MILVUS_URI=http://localhost:19530

You'd need a Milvus server running first, for example in Docker. The project has no docker-compose file yet, so I'd have to add one.

Things to know:
- Restart needed. Restart the API after editing .env, because settings are read once at startup.
- Nothing carries over. Switching from the local file to a server starts with an empty collection. Anything already stored in data/milvus.db isn't copied across.
- No auth setting. The code passes the URI straight to MilvusClient(uri), with no token option. A server that needs a login, such as Zilliz Cloud, would need a small MILVUS_TOKEN setting added. Say so if you want that.

✻ Cogitated for 11s · done 1:32 PM

※ recap: The goal is a stock briefing app that cites SEC filing evidence, and the SEC datasets are now loaded into SQLite with your .env created. Next, fill in GOOGLE_API_KEY and SEC_USER_AGENT in .env, then fetch company_tickers.json so ticker lookups work.

❯ Golden dataset to evalute the model resonse. sec-golden.jsonl

I'll look for the file first.

  Listed 1 directory

There are two copies. I'll compare them and look at the structure.

  Ran 1 shell command

The two copies are byte-identical, with 15 records. I'll read the whole file, since it's small.

  Read 1 file

I'll verify the 15-question golden set against the raw SEC data, confirming each evidence row exists exactly once and matches its expected answer before using it for scoring. · summary

  Ran 2 shell commands

I haven't built an evaluator yet. First I checked the golden set against the raw SEC files, and it holds up.

Validation results:
- Evidence rows: all 26 evidence rows in sec-golden.jsonl exist in the raw sub.txt, num.txt, pre.txt and tag.txt, each matching exactly one row.
- Answers vs evidence: every expected_answer agrees with its evidence. SEC-13 recomputes as 109,417,000,000 - 111,184,000,000 = -1,767,000,000.

- Uniqueness: Apple has exactly one 10-Q in each quarter, so none of the "when did Apple file…" questions is ambiguous.
- SEC-14: the sentence from the PDF's Overview section is in the PDF.
- SEC-15: the "abstain" case is sound. No Apple figures dated 2027 or later exist in any of the three quarters.

The two copies (~/Downloads and ~/Documents/Codex/…/outputs) are byte-identical, and I haven't copied the file into the project.

What the set covers: every question is about Apple. There are 13 table lookups from the SEC files, 1 question answered from the PDF (SEC-14) and 1 abstention (SEC-15). Nothing tests the briefing's narrative claims or its citations.

One decision before I build anything: the app turns a ticker into a cited brief, and it has no way to answer a question like "When did Apple file its Q2 10-Q?" These 15 questions need one. Which do you want?

1. Data layer only. A script that runs all 15 questions against data/fsds.sqlite with no LLM and scores them. It runs today and guards the SQLite load against regressions. This is my recommendation, but it won't test the model.
2. Add a question-answering path. Gemini would answer from the SQLite data (including declining when evidence is missing), and a scorer would grade it against the golden answers. This tests the model, but it needs a new code path and your Gemini key, which .env doesn't have yet.
3. Evaluate the brief itself. The golden set doesn't fit this, so I'd first need to write briefing-style golden cases with you.

If you choose 1 or 2, I'll put the file at stock-briefing/tests/golden/sec-golden.jsonl.

✻ Cooked for 2m 9s · done 1:45 PM

❯ these is just a sample set to test the model before deploying. nothing like checking everytime with exact questions.

Understood. You want the exact 15 questions re-run through the model as a pre-deploy check, not a data-layer test. To keep that small, I'll see what the app's LLM layer already offers.

  Ran 1 shell command

The codebase has new additions since I last checked—use_fsds, llm_fallback_models, and fsds wiring in services. I'll review the current FSDS API and check whether the Gemini key is set before making any changes. · summary

  Ran 1 shell command

Both the Gemini key and the SEC User-Agent are now set, and the suite is at 69 passing. I'll look at the existing Gemini check script so the eval uses the same calling conventions.

  Ran 1 shell command

I'll copy the golden files into the project and review the existing helpers so the pre-deploy check—which runs the 15 questions through your Gemini models, builds evidence from the SQLite data, and scores the answers—can reuse them in tests. · summary

  Ran 1 shell command

Now the pure-logic module: loading, evidence-pack building, and scoring. It has no network or LLM dependency, so it can be unit-tested.

● Write(briefing/golden.py)
Wrote 268 lines to briefing/golden.py
"""Golden-set evaluation, minus the model call: load questions, build the evidence the model is
given, and score what comes back.

he
data layer as well as the model) and the answer is scored by rule, not by another LLM. Scoring i
s
deliberately lenient about *format* (a date as 2026-01-30 or "January 30, 2026"; a figure as
right label, abstaining when the files cannot answer).

What this does not test: retrieval over free text (Milvus) and the narrative briefing itself.
… +283 lines

I'll simplify the sign logic in the figure parser and fix it so a spaced dash (e.g. Q2 – 111,184) isn't mistaken for a negative sign—only a minus directly attached to the number will count. · summary

● Update(briefing/golden.py)
Added 4 lines, removed 1 line

_SCALE = {"trillion": 10**12, "billion": 10**9, "bn": 10**9,
"million": 10**6, "thousand": 10*
*3}
_NUM = re.compile(r"(?P<neg>[-−]|\()?\s*\$?\s*(?P<neg2>[-−])?\s*(?
P<n>\d[\d,]*(?:\.\d+)?)\s*

```
(?P<scale>trillion|billion|million|thousand|bn)?\b", re.I)
# A minus counts only when attached to the figure ("-$1,767",
"$-1,767", "(1,767)"), so "Q2 -
111,184" stays positive.
_NUM = re.compile(
    r"(?<![\w.])(?P<neg>[---(])?(?:\$\s?(?P<neg2>[---])?)?(?
P<n>\d[\d,]*(?:\.\d+)?)\s*(?P<scal
e>trillion|billion|million|thousand|bn)?\b", re.I
)
_MONTHS = {m: i for i, m in enumerate(["jan", "feb", "mar", "apr",
"may", "jun", "jul", "aug",
 "sep", "oct", "nov", "dec"], 1)}



● Update(briefing/golden.py)
Added 1 line, removed 1 line
            continue
        if m["scale"]:
            v *= _SCALE[m["scale"].casefold()]
        out.append(-v if (m["neg"] and m["neg"] != "(") or m["neg2"]
or m["neg"] == "(" else v
)
        out.append(-v if m["neg"] or m["neg2"] else v)
    return out



Now the runner script, which also serves as the pre-deploy gate: it
exits non-zero when the pass rate falls below the threshold.

● Write(scripts/eval_golden.py)
Wrote 164 lines to scripts/eval_golden.py
"""Pre-deploy check: run the exact golden questions through the
configured Gemini model(s) and sc
ore them.
    python scripts/eval_golden.py                    # all questions,
needs GOOGLE_API_KEY and da
ta/fsds.sqlite
    python scripts/eval_golden.py --dry-run          # no model call:
only checks the model would
    python scripts/eval_golden.py --only SEC-06 SEC-13
    python scripts/eval_golden.py --show-pack SEC-13 # print the
sources the model sees for one q
uestion
Exit code 0 only when the pass rate reaches --min-pass (default 100%),
so it can gate a deploy.
Models are tried in the order of LLM_MODEL then LLM_FALLBACK_MODELS,
as the app does.
… +183 lines
```

● Update(.gitignore)
Added 1 line
data/raw/
data/cache/
data/uploads/
data/eval/
data/*.sqlite
data/*.sqlite-*
data/milvus.db*

One tidy-up (a redundant exception tuple), then a dry run. That uses no model calls and tells me whether the model would actually be given the evidence for all 15 questions.

● Update(scripts/eval_golden.py)
Added 1 line, removed 1 line
        return 1
    try:
        chunks = load_doc_chunks(args.doc)
    except (OSError, FileNotFoundError, Exception) as exc: # noqa:
BLE001 - pdftotext missing
 or file absent
    except Exception as exc: # noqa: BLE001 - pdftotext missing or
file absent
        print(f"warning: documentation not loaded
({exc.__class__.__name__}); documentation qu
estions cannot pass")
        chunks = []
    statements = tuple(x.strip().upper() for x in
args.statements.split(",") if x.strip())

  Ran 1 shell command

The evidence is present for all 15. I'll look at what the model actually sees for one question, to make sure the pack is sensible and doesn't pull in the wrong company.

  Ran 1 shell command

The pack looks right: only APPLE INC is matched, its three 10-Qs are included, and the model has to pick the correct qtrs=1 figure itself. Next, offline unit tests for the scoring and pack logic.

● Write(tests/test_golden.py)
Wrote 131 lines to tests/test_golden.py
from decimal import Decimal
from pathlib import Path

import pytest

```
    Golden, build_pack, evidence_in_pack, find_companies, format_pack,
load_doc_chunks, load_gol
den,
    parse_amounts, parse_dates, pick_doc_chunks, score_answer,
)
from briefing.sources.fsds import FsdsStore, connect, ingest_quarter
… +141 lines

One assertion in that test is sloppy (an or that can't fail). I'll
tighten it before running.

● Update(tests/test_golden.py)
Added 1 line, removed 1 line


def test_a_spaced_dash_or_quarter_name_is_not_a_minus_sign():
    assert parse_amounts("Q2 - 111,184,000,000 USD") == [Decimal(2),
Decimal(111_184_000_000)]
or Decimal(111_184_000_000) in parse_amounts("Q2 - 111,184,000,000
USD")
    assert Decimal(111_184_000_000) in parse_amounts("Q2 -
111,184,000,000 USD")
    assert Decimal(-111_184_000_000) not in parse_amounts("Q2 -
111,184,000,000 USD")
    assert Decimal(-3) not in parse_amounts("Q2-Q3 and 2026-01-30")


  Ran 1 shell command

Found two real bugs: label scoring was too lenient on wrong answers,
and company matching could return multiple matches instead of the
longest one. I'll fix both—requiring exact matches for label-style
answers and making the longest company name win. · summary

● Update(briefing/golden.py)
Added 7 lines, removed 4 lines
    """Companies whose name (minus Inc/Corp/...) appears as whole
words in the question. Best
effort."""
    q = question.casefold().replace("’", "'")
    rows = store.conn.execute("SELECT cik, name, COUNT(*) AS n FROM
filings GROUP BY cik, name
 ORDER BY n DESC").fetchall()
    hits: list[tuple[str, str]] = []
    hits: list[tuple[str, str, tuple[int, int]]] = []
    for r in rows:
        stem = _stem(r["name"])
        if len(stem) >= 3 and re.search(rf"(?<!\w){re.escape(stem)}(?!
\w)", q):
```

```
            hits.append((r["cik"], r["name"]))
    return hits[:limit]
        m = re.search(rf"(?<!\w){re.escape(stem)}(?!\w)", q) if
len(stem) >= 3 else None
        if m:
            hits.append((r["cik"], r["name"], m.span()))
    # "Acme Holdings" also contains "Acme": the longest name wins
where one match sits inside
another
    keep = [h for h in hits if not any(o is not h and o[2][0] <= h[2]
[0] and h[2][1] <= o[2][1
] and o[2] != h[2] for o in hits)]
    return [(cik, name) for cik, name, _ in keep][:limit]


def fmt_value(v: float) -> str:
```

● Update(briefing/golden.py)
Added 4 lines, removed 1 line

```
        ok = want in parse_amounts(answer)
        return Score(ok, "" if ok else f"figure {want:,} (with that
sign) not found in the ans
wer")
    e, a = _norm(expected), _norm(answer)
    ok = a == e or (e in a and len(a) <= 4 * len(e) + 40)
    if expected.rstrip().endswith("."):  # a sentence: the expected
wording must appear, with
some room for phrasing
        ok = e in a and len(a) <= 4 * len(e) + 40
    else:  # a label: exactly as written, because "Total net sales" is
not "Net sales"
        ok = a == e
    return Score(ok, "" if ok else "answer does not match the expected
text")
```

  Ran 1 shell command

All 100 tests pass (the original 69 plus 31 new). Now the real check: the 15 exact questions through your configured Gemini models, about 15 small calls using the key in your .env.

  Ran 1 shell command

All 15 tests pass, but the primary model gemini-flash-latest answered none of them (relying on fallbacks instead), with some responses taking 90 seconds. I'll update the script to log why the primary model is failing. · summary

Ran 1 shell command

The grep doesn't show the ask return edit, so I'll confirm it applied, then run two questions to see why the primary falls through.

Ran 1 shell command

Found it: the 90-second delays trace to quota/429 and 503 errors on this key for several Gemini models, with the first run only passing because fallbacks caught some questions. I'll fix the script to give model outages a distinct exit code and timestamp report files so they stop overwriting each other. · summary

Ran 1 shell command

The README was already updated to document the golden-set eval, so I'll review that section to add the new exit code and timestamped reports without duplicating or overwriting existing content. · summary

Read 1 file

Two lines there are now out of date: the report path, and "a live pass rate has not been recorded". I'll update just those.

● Update(README.md)
Added 2 lines, removed 2 lines
- Fifteen questions about Apple's fiscal Q1 to Q3 2026 filings cover filing dates, quarterly n
et sales, the filer's line labels, taxonomy labels, a signed change between quarters, a docume
ntation question, and one question that **should be refused** (fiscal Q1 2028 is not in the fi
les).
- The evidence pack is built deterministically from `data/fsds.sqlite` plus the data-set docum
entation PDF (via `pdftotext`), then scored by rule.
- A pass needs a correct answer **and** a citation to a source the model was actually given.
- The run is written to `data/eval/last-run.json`, and the exit code can gate a deploy.
- **Current state:** `--dry-run` confirms the evidence is present for 15 of 15 questions. A li
ve pass rate has not been recorded yet, so run the live check before quoting a number.
- Each run is written to `data/eval/golden-<timestamp>.json`, with the model that answered eac
h question and which models failed first. The exit code can gate a deploy: `0` passed, `1` wro
ng answers, `2` not evaluated because models errored (quota 429, overload 503).

- **Current state:** `--dry-run` confirms the evidence is present for 15 of 15 questions. The
first live run on 2026-11-02 passed 15 of 15, but `gemini-flash-latest` answered none of them.
 It returned quota (429) or overload (503) errors, so `gemini-3.6-flash` and `gemini-flash-lit
e-latest` answered, and some answers took about 90 s. Treat the pass rate as a property of the
 fallback chain, and re-run when the primary model has quota.
- **What it does not test:** Milxt, and the narrative briefing itsel
                                                                    Update
available! Run: brew upgrade claude-code
──
──

❯

  - The idea: the problem, the six principles that rule out invented figures and links, and the scope you
    decided.
  - Architecture: a system diagram, both LangGraph graphs with a node-by-node table, the evidence model, how
    each of the seven facets retrieves its sources, and a sequence diagram of a first lookup.
  - Tech stack: each layer with the reason it was chosen.
  - How trust works: what each citation looks like, how verification checks it, and what verification does not
    prove.
  - Improvements by stakeholder: each item is a concern, what was built, and the file it lives in. The groups
    are advisors, compliance, engineering and IT, data and model quality, and leadership.
  - Also covered: data sources and how fresh they are, a design trade-offs table, the evaluation and tests, and
    known limits plus the roadmap.

  What you should check:
  - Stakeholder improvements: the repo holds no record of what stakeholders actually asked for, so I wrote those
    tables from what the code does and from your Q&A decisions. The five group names and the wording of the
    concerns are mine. If real feedback drove any of these changes, edit those tables so they say so.
  - Golden-set pass rate: a live pass rate has never been recorded (there is no data/eval/last-run.json). The
    README says only that all 15 questions have their evidence available. A live run would give you a pass rate
    to put in.
  - Verified against the code: the retry rules, the request limit, the

sections that get indexed and the FSDS
    coverage. FSDS coverage is 17,011 filings from 2026-01-02 to
2026-09-30.

✻ Baked for 4m 43s · done 2:01 PM

                                                    control this
session from your phone · /remote-control
──
──

❯

──
──
  ▸▸ auto mode on (shift+tab to cycle) · ← for agents